

Bid Evaluation Report		
Evaluation Report – Renovation of Azizabad Branch Karachi		
1	Name of Procuring Agency	Sindh Bank Ltd.
2	Tender Reference No.	SNDB/COK/ADMIN/TD/1237/2022
3	Tender Description	Renovation of Azizabad Branch Karachi
4	Method of Procurement	Single Stage One Envelope Bidding Procedure
5	Tender Published / SPPRA S.No	T00531-21-0006. Express Tribune, Daily Express, Sindh Express (01/02/2022)
6	Total Bid Documents Sold	02
7	Total Bids Received	02
8	Technical/Financial Bid Opening Date & Time	22/02/2022 at 1100 Hrs
9	No. Of Bid qualified	02
10	Bid(s) Rejected	00

Detail on the above is as follows:-

S No	Name of Firm or Bidder	Qualified / Disqualified in Technical / Eligibility Inspection	Cost offered by the Bidder	Ranking in terms of cost	Comparison with Engineering Estimated cost (Rs.3,605,200/-)	Reasons for acceptance/ rejection	Remarks
0	1	2	3	4	5	6	7
1.	M/s. Jawed Construction Co	Qualified	Rs.3,955,775/- (Area 1,400 sq.ft x Rate per sq.ft Rs.2,825.5535/-)	1 st Lowest	Rs.350,575/- Above the estimated cost	Accepted Most Advantageous Bid well within 15% limit	Accepted for Contract Award
2.	M/s.G.A Woods	Qualified	Rs.3,992,760/- (Area 1,400 sq.ft x Rate per sq.ft Rs.2,851.9714/-)	2 nd Lowest	Rs.387,560/- Above the estimated cost	2 nd Lowest	-

Accordingly, going by the Technical/Financial Evaluation criteria laid down in the tender document, M/s. Jawed Construction Company is the most advantageous bid i.e. Rs.3,955,775/-, hence recommended for Renovation of Azizabad Branch Karachi.

Members Signature- Procurement Committee

Arshad Abbas Soomro
Head of Administration

Dilshad Hussain Khan
Chief Financial Officer




Syed Muhammad Aqeel
Chief Manager, IDBL Karachi

Handwritten signatures of the Procurement Committee members, including a date stamp '11/4/22'.

SUMMARY OF EVALUATION FOR RENOVATION OF AZIZABAD BRANCH KARACHI

S.No	Contractors	Status of Firm		Years in Business(Only Dealing in Financial Institution)			Branches up till now Constructed/renovated for the banks/financial institutions in last 5 years		Average Turn Over in last three years			Number of Banks/DFI currently on active Cliental List			Grand Total	Qualified (70%) marks / Disqualified
		Total Points		Total Points			Total Points		Total Points			Total Points				
		Private Limited / Partnership	Sole Proprietorship	10 years & above	8 Years & above	6 Years & above	25 Branches & Above	15 Branches & Above	4 million & Above	2 million & Above	3 Above	2	1			
1	Jawed Construction Company	10	7	20	20	20	40	30	20	20	5	5	82	Qualified		
2	G.A Woods	7	7	20	20	20	30	30	20	20	10	10	87	Qualified		

Members Signature- Evaluation Team

 M. Athar Iqbal
 Admin Division
 Fozia Shaqim
 Operation Division
 Taimoor Ghousi
 Finance Division

Members Signature- Procurement Committee


 Arshad Abbas Soomro
 Head of Administration
 Dilshad Hussain Khan
 Chief Financial Officer
 Syed Muhammad Aqeel
 Chief Manager, IDBL, Karachi


MANDATORY / DISQUALIFICATION CONDITIONS


RENOVATION OF AZIZABAD BRANCH KARACHI

S.No	Contractors	Black Listing Affidavit (Yes/No)	FBR Registration/ Provincial Revenue Collecting Authority (Yes/No)	Alternate Bid Offered (Yes/No)	Tender Fee Submitted (Yes/No)	2 X Warning Letters issued by SNDB (Yes/No)	Blacklisted on SPPRA/Sindh Bank Ltd (Yes/No)	Qualified / DisQualified
1	Jawed Construction Company	Yes	Yes	No	Yes	No	No	Qualified
2	G.A Woods	Yes	Yes	No	Yes	No	No	Qualified

Members Signature- Evaluation Team



 M. Athar Ubbal
 Admin Division



 Fouzia Shamim
 Operation Division


 Taimoor Ghausi
 Finance Division

Members Signature- Procurement Committee

1. Arshad Abbas Soomro
 HEAD OF ADMINISTRATION


 2. Dilshad Hussain
 CFO


 3. Syed Muhammad Aqeel
 Chief Manager, IDBL

ATTENDANCE SHEET
 BID OPENING -

FOR SELECTION OF Renovation of Azizabad Branch UHI

Date: 22/02/22

S.No	Company Name	Name of Company Representative	Contact No.	Company Address	Signature
01	M/s. Jawad Construction Co				
	G.A Woods				

Signature - Procurement Committee Members

Head of Administration

Chief Financial Officer

Chief Manager (IDBL)

MINUTES OF THE OPENING OF THE TENDER (TECHNICAL /FINANCIAL PHASE)

TYPE OF PROCUREMENT

ADMIN / IT / CONSULTANT / MEDIA

TENDER NAME

Renovation of Azizabad Brest WHI

TYPE OF TENDER

SINGLE STAGE-ONE ENVELOPE / SINGLE STAGE-TWO ENVELOPE / TWO STAGE / TWO STAGE-TWO ENVELOPE

OPENING DATE

22/2/22

OPENING TIME

11 00 hrs.

ATTENDANCE (MEMBER PC)

TYPE

TYPE

TYPE

TYPE

ATTENDANCE (REPS. OF BIDDERS)

NAME

FIRM

BID OFFERED

①

<u>Javed Constructive Co</u>	/	<u>3,955,775/-</u>
<u>C.A Woods</u>	/	<u>3,992,760/-</u>
/	/	/
/	/	/
/	/	/
/	/	/

TOTAL BIDS ACCEPTED FOR EVALUATION

TO BIDS REJECTED

REMARKS

SIGNATURE MEMBERS PO-ADMIN
 Head - Fin Div. _____
 Head - Admin Div. _____
 Member-1/2/3 _____

(

)

COMPARISON OF COST OF RENOVATION WORKS- AZIZABAD BRANCH - SINDH BANK LTD			
S#	DESCRIPTION	JAWED CONSTRUCTION COMPANY	G.A WOODS
		AMOUNT	AMOUNT
A	CIVIL WORKS	2,350,350	2,493,860
B	PLUMBING WORKS	304,500	242,000
C	ELECTRIAL WORKS	1,087,050	1,005,650
D	HVAC	213,875	251,250
	TOTAL RENOVATION COST	3,955,775	3,992,760

SIGNATURE MEMBERS PC-ADMIN

Head - Fin Div. _____

Head - Admin Div. _____

Member-IDBL. _____

Date: _____

BILL OF QUANTITY
Comparison of Cost of Renovation Works- Azizabad Branch

S#	DESCRIPTION	UNIT	QTY.	JAWED CONSTRUCTION COMPANY		G.A WOODS	
				RATE	AMOUNT	RATE	AMOUNT
A	CIVIL WORKS						
1	Dismantling / Removal Works. Dismantling / Removal of existing Block/Brick masonry, ceiling , R.C.C slab, projection ,sub floor cutting, chipping of plaster.where required, Doors & windows with frame in any shape, Iron grills, mosaic skirting, Dado & all sanitary fixtures, water & drainage line, entire electrical wirings, disposed off useless materials/debris outside the municipal limits and stack useable materials as decided by bank's engineer. complete in all respect.(Contractor must visit the site prior to quote the rate).Salvage material to be returned to landlord or Bank as the case may be.	Job	1	65,000	65,000	80,000	80,000
2	Termite Proofing Providing and carrying out termite proofing using FIPROKILL/ BIFLEX / DURSABANE with a solution of 1 gallon of chemical to 50 gallons of water, sparing this solution @ 2 liters per sq. meter area (or liters per 10.76 sq. Area) with a pressure ensuring at least 3" penetration in the soil of the area to be treated. The contractor will provide a guarantee for a period of ten years against infestation of termite in the shape and mode approved by the Engineer, stating that in case of infestation, additional treatment will be provided by the contractor at no extra cost to the Client (horizontal & Vertical).	SFT	1400	25	35,000	15	21,000

SIGNATURE MEMBERS
 Head - Fin Div. _____
 Head - Admin Div. _____
 Member-IDBL _____
 Date: _____

S#	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT	RATE	AMOUNT
3	<p>Plain cement Concrete (Cement as per Market rate) Providing, laying, average 4" thick Flooring (1:3:6) at wash room, kitchen raised floor of 1250 psi compressive strength under any type of flooring using best Quality OPC/Sulphate Resistant cement and local approved quality sand and crushed stone, form work and its removal, with necessary arrangements where required excluding base of tiles complete in all respects as per approval of bank's engineer.</p> <p>Cement: Falcon, Lucky Pakland, D.G Khan Sand: Hyderabad Bolari /Mairi River/Hub Crush: Hub 3/4" and Kot Banglo for Interior Sindh</p>	CFT	100	400	40,000	370	37,000
4	<p>REINFORCED CEMENT CONCRETE (Vault Room as per Layout Plan). Providing and laying, compacting finishing & curing etc. straight or curved cast- in place designed mix 1:2:4 Reinforced Cement Concrete using 1 Part of Ordinary Portland Cement or equivalent, 2 Parts of silt free local sand and 4 Parts of 3/4" thick downgraded crushed stone; mixed in a manner to achieve a cube strength of 3000 psi in 28 days, including mixing, transporting, hoisting, lifting & placing at any height / depth, vibrating and curing etc. Complete in all respect including cost of Steel Reinforcement (3/8" dia steel bars G-60 @ 6" C/C both ways, staggered double jaal in a manner that the alternate spacing b/w bars should not increase 3" C/C) & form work for Cement Concrete including cutting, bending, laying in position, making joint and fastening, removal of rust from bars, cost of binding wire and labor charges for binding of steel reinforcement: also includes cost of form work and its removal. Complete in all respects, 9" thick walls, and column or as per direction of Engineer</p>	CFT	210	900	189,000	790	165,900

SIGNATURE MEMBERS PG-ADMIN

Head - Fin Div. 

Head - Admin Div. 

Member-DBL 

Date: _____

S#	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT	RATE	AMOUNT
5	Block / Brick Masonry works. Providing & laying Block / Brick masonry walls including racking of joints with 1:4 cement sand mortar, the job includes Two 3/8" dia steel bars of 2'-0" length on both sides of wall at every 3'-0" ft height for anchoring of masonry with the sides and Two 3/8 " dia bars of 2'-0" length at every third block length for anchoring masonry walls to plinth/floor beams, complete in all respect as per drawing, specifications, to the satisfaction of Architect / bank's engineer.						
4.1	4" thick Block Masonry internal walls (First class Machine made Blocks)	SFT	700	145	101,500	160	112,000
4.2	6" thick Block Masonry external walls (First class Machine made Blocks)	SFT	0				
6	Plaster Works. Providing & laying 3/4" thick cement sand plaster (Internal / External) with 1:4 cement sand mortar on walls, columns, beams, using best quality O.P.C, including 6" inches wide mesh at joints of structure with block masonry and over conduiting ,smooth trowel finish complete in all respect. (This includes all the base plaster require for making diagonal and alignment for the existing walls) as per satisfaction of Architect / bank's engineer.	SFT	1850	65	120,250	65	120,250
7	Flooring, Elevation & Special Finishes. Providing and laying glazed full body Porcelain tiles 24" X 24" at floor, of approved design, colour and pattern, china bone colour or Master or equivalent full body porcelain , setting in Sile dry bond (with cement), with matching color imported Grout. Complete in all respect, including curing, cleaning, finishing & hacking/chipping of existing surface for bonding where necessary, and 4 inches wide skirting at walls of the same tiles as above mentioned, with 1:2:4 PCC 50 mm thick, etc. as per specifications and/or as directed by the Architect / Engineer (at any elevation)	SFT	1400	330	462,000	380	532,000

SIGNATURE MEMBERS PC ADMIN

Head - Fin Div.

Head - Admin Div.

Member-IDBL.

Date:

S#	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT	RATE	AMOUNT
9	FALSE CEILING Gypsum Board (24"X24")						
	Providing & laying 8 mm thick gypsum board False Ceiling, 24" x 24" Elephant Brand or approved equivalent in straight, curved, tiles or multiple profiles, as shown on drawing section, fixed with imported powder coated, with groove, aluminum, "T" & "L" section with ceiling suspension system having provisions for light and AC grill. Complete in all respect as per drawing and instruction of Bank's Engineer.	SFT	1400	140	196,000	150	210,000
9	Ceramic Tiles						
a	Toilet: Providing / Laying wash room tiles (HMD45-117 9"x17" SB for floor & walls upto 7 feet height (Master brand) or equivalent as per approved shade & layout pattern with 2" thick base concrete including grouting of joint with matching grout material of Stile, complete in all respect as per satisfaction of Architect / bank engineer.	SFT	300	320	96,000	325	97,500
b	Kitchen/Pantry: Providing / Laying Pantry tiles (HMD38-50SF 9" x 17" SB for floor & walls upto 5 feet height (Master brand) or equivalent as per approved shade & layout pattern with 2" thick base concrete including grouting of joint with matching grout material of Stile, complete in all respect as per satisfaction of Architect / bank engineer.	SFT	60	330	19,800	325	19,500

SIGNATURE MEMBERS PCADMIN

Head - Fin Div, _____

Head - Admin Div, _____

Member-IDBL, _____

Date: _____

S#	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT	RATE	AMOUNT
10	Marble Providing & fixing pre polished 3/4" thick Marble Top quality with approved size and shade over 2" thick pre cast RCC slab including 1/2" thick gola, grouting and jointing including cost of cutting of marble for basin and sink bowl including filling with silicone around joint of marble complete in all respect as per satisfaction by the engineer. Pantry Counter Top (Boticina)	SFT	20	600	12,000	525	10,500
11	MDF Low Height Partition 3' high Between Tables. (If required) Provide and install 2" x 2" partal wood Solignum treated frame for wooden partitions spaced no more than 16" on centre vertically and 24" on centre in the horizontal dimension fixed in plumb and level. With water based matt finish paint. Complete in all respect with good work man ship and as per details mentioned in drawing.	SFT	32	750	24,000	690	22,080
12	WOODEN CABINETS Kitchen Cabinets Lower Unit: Providing, fabricating and fixing in position pantry cabinets 24" deep 32" high consisting of 3/4" thick laminated board (Furniture color) of SONEX, Noor or equivalent on front shutter and drawers, Dark grey on internal box and shelves moulding 1/2"x3/4" including nails, screws, bolts, imported hinges, catchers, locks, handles, 3 coat of sprit polish of matching shade of furniture color on wood lipping and wood preservative treatment including premium quality ceramic tiles above 4" thick P.C.C floor platform complete in all respects as per drawings and as directed by the bank's Engineer. etc. Complete in all respects.	SFT	18	1,000	18,000	950	17,100

SIGNATURE MEMBERS **RC ADMIN**

Head - Fin Div. _____
 Head - Admin Div. _____
 Member-IOBL. _____
 Date: _____

S#	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT	RATE	AMOUNT
b	<u>Upper Unit:</u> Providing and fixing in position pantry cabinets 12" deep and 24" high (Hanging) consisting of 3/4" thick laminated board (Furniture color) of SONEEX, AL Noor or equivalent on front shutter and drawers, Dark grey on internal box and shelves moulding 1/2"x3/4" including nails, screws, bolts, imported hinges, catchers, locks, handles, 03 coat of sprit polish of matching shade of furniture color on wood lipping and wood preservative treatment complete in all respects as per drawings and as directed by the bank's Engineer.	SFT	20	1,000	20,000	950	19,000
13	<u>Paint at Walls</u> Providing and applying, 3 coats of ICI Matt Finish Paint Ash White (3130) or BERGER or equivalent of approved colour and shade, at any floor & at any height over one coat of primer and making smooth and even surface by applying ICI Paintex base filling as per specifications, to surface of walls, complete in all respects as specified and as approved by the bank's Engineer.	SFT	2800	50	140,000	50	140,000
14	<u>WOODEN DOOR / FRAME / CHOWKAT / Beading</u> DOOR FRAME: Providing and fixing of required width, 16 SWG, GI door frames for Toilets, kitchen, stores & cash counter with polishing, including Lintels, hold fasts, where ever required, complete in all respect including painting / polish with proper beach / diyar wood beading.	NO	5	8,000	40,000	7,500	37,500
b	SKIN DOORS, 1-1/2 inches thick (for Toilets, Kitchen, stores & cash counter) Provide and install doors consisting of best quality Malaysian skin, pressed over best quality treated partial wood framing, with approved quality of door locks, handle, tower bolt, hold fast, stopper, hardware and paint /polish, complete in all respect.	SFT	105	600	63,000	520	54,600

SIGNATURE MEMBERS PC-ADMIN

Head - Fin Div. 

Head - Admin Div. 

Member-IDBL. 

Date: _____

S#	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT	RATE	AMOUNT
15	Wooden Hanging Beams. Providing & fixing in position wooden Beams for support to fix glass and glass door consisting of 1 1/2 x3" @ 2'-0" c/c partial wood framing and 1/2" MDF Lasani board (Malaysia) on both sides including nails, bolts, glue wastage, wood preservative, treatment & 3 coats of paint complete in all respect as per drawings and as directed by Bank's Engineers.	RFT	35	600	21,000	620	21,700
16	INSTALLATION OF VAULT ROOM DOOR Lifting & Fixing charges of Bank's supplied Vault / Locker Doors, welding of door frame with RCC MS bars, and to facilitate the Vendors. Complete in all respects.	NO	1	15,000	15,000	7,000	7,000
17	GLASS DOOR (BM Cabin, ATM front) Providing, fabrication & fixing 12 mm thick glass door with top & bottom locking system, 4" Aluminum D-48 by Lucky or equivalent section, with 12mm thick Middle East / Saudi Arabia or equivalent clear glass with frost film and Bank's monogram, Approved Ajrak film, with gasket size and shape as shown on drawing, including bolts, D lock, nuts, screws aluminum channel, handle, floor machine (New Star or equivalent), locks etc. Complete in all respects as directed by Engineer.	SFT	84	1,350	113,400	1,320	110,880
18	GLASS PARTITION Providing and installation 12mm thick glass KSA/UAE or equivalent polished glass with 100mm top & bottom rails, brush finish SS-304, lucky or equivalent section with frosted film surface as per approved design. Contractor is required to provide joints between the panels with minimum 5mm thick clear silicon from Dow corning or other approved by the Engineer. Complete in all respects.	SFT	200	850	170,000	750	150,000

SIGNATURE MEMBERS 

Head - Fin Div. 

Head - Admin Div. 

Member-IOPL. 

Date: _____

S#	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT	RATE	AMOUNT
20	Wrought Iron Grills for external windows, AC outers (If necessary) Approved design grills for all external windows & AC Outers/exhaust fans (if required). The security grills will be installed from inside so that glass will be visible from outside. MS Grill comprising of 1/2" solid square bars @ 6" c/c 1"x1-1/2" MS 16 gauge angle iron, welding, grinding, finishing, rubbing 3 coat of enamel paint (ICI,NIPPON,BERGER or equivalent) red oxide before paint. Complete in all respects, as per standardized design and /or as shown in drawing as per approved design, attached herewith. Further proper lockable grills with above specification will also be provided for all AC outdoor units.	SFT	170	600	102,000	580	98,600
22	M.S DOOR on Emergency exit, ATM internal & Guard Post						
	Fabricating, providing and fixing MS door with 16 S.W.G M.S 3/4" square pipe, 16 SWG MS sheet pressed over this frame including metal door frame, at both sides, sheet frame painted with approved enamel color including 2" x 5" eye level opening with proper MS shutter of 16 swg sheet to look outside , including best quality hinges, locks, handles, hold fasts and other necessary hardware etc. size as per site. Complete in all respects as per drawing attached herewith, specifications and as directed by the Bank.	SFT	57	1,200	68,400	65,550	65,550
23	MARBLE AT ENTRANCE/Stair STEPS						
	Providing and laying 20mm thick Marble of approved quality and size on any type of flooring straight or curved, as per drawings, laid with cement slurry over cement sand mortar (1:4), including filling of joint with grouting material, rubbing, rounding and final chemical polish etc, complete in all respects.	SFT	140	600	84,000	780	109,200
24	Metal Stair Case GF to MF height 7'-6"						
25	Providing & installation of Spiral Stair metal pipe 5" dia heavy duty MS pipe stair dia 6ft with metal steps with checkered plate at top with rail pipe, including paint work complete in all respect	Job	1	90,000	90,000	190,000	190,000
26	ATM ACCESS RAMP FOR DISABLED PERSON						
	A three feet wide CC ramp, at 30 degree, will be provided for disabled person. The ramp tiles will be grooved tiles and , SS railing will be provided Cost includes all said material, complete in all respect.	JOB	1	45,000	45,000	45,000	45,000
	TOTAL CIVIL WORKS				2,350,350		2,493,860

SIGNATURE MEMBERS

Head - Fin Div. _____

Head - Admin Div. _____

Member-ICU. _____

Date: _____

BILL OF QUANTITY
Comparison of Cost of Renovation Works- Azizabad Branch

S.No.	DESCRIPTION	UNIT	QTY	JAWED CONSTRUCTION COMPANY		G.A WOODS	
				RATE	AMOUNT	RATE	AMOUNT
1(a)	Providing and fixing European type ceramics ware coupled water closet, (PORTA) or equivalent , white / light colour, including 3 gallons cistern, P/S trap, C.P tee stop cock with wall cups, connection pipes, "SONEX", "MASTER (Royal)", hinged double bacolite seat and cover of best quality, all joints to services and drains, plugging and screwing as necessary to the structure and make good the same, complete in all respect as per specifications and drawings.	Nos	1	25,000	25,000	20,000	20,000
(b)	Providing and fitting Glazed earthen ware water closet, squatter type (Orisa pattern), combined with foot rest, Best Quality including Plastic made Flushing tank, SONEX tee stop cock for cistern water inlet and C.P connector with nuts and fitting, approved other ancillary material complete in all respect.	Nos	1	17,000	17,000	15,000	15,000

SIGNATURE MEMBERS PC-ADMIN
 Head - Fix Div. _____
 Head - Admin Div. _____
 Member-IOBL _____
 Date: _____

S.No.	DESCRIPTION	UNIT	QTY	JAWED CONSTRUCTION COMPANY	G.A WOODS
2	Providing and fixing Wash hand Basin Vanity type, PORTA or equivalent white colour "SONEX" / "MASTER" waste coupling, plug with C.P brass chain, 1.5" dia. P.V.C (D type) waste pipe connections to water lines, tee stop cock for cold and hot water inlet connector with nuts and fitting, waste pipe waste coupling , plugs with chain other ancillary material C.P grating including C.P bottle trap, testing etc. complete in all respect and as directed by the Engineer.	Nos.	2	18,000 36,000	16,000 32,000
3	Provide & fix best quality Stainless Steel imported Kitchen Sink, Balraco or equivalent make (40" x 20") 1000mm x 500mm sink with CI or WI brackets 150mm (6") built in wall, 40mm(1 1/2") rubber plug & chrome plated brass chain, 40mm (1 1/2") C.P brass waste, pillar tap 2 way deluxe, 40 mm (1 1/2") dial malleable iron or C.P. brass trap, Bottle trap and unions. Make requisite holes in walls & floor for pipe connections & make good with approved material. (with SONEX fittings).	Nos.	1	9,000	6,500 6,500
4	Provide & fix uPVC floor drains of 4" dia of make Nikkassi or approved equivalent, having minimum guaranteed 2" water seal with screw down C.P cover, peripheral drains with or without a vent arm. Make requisite holes in walls, floor for pipe connections & make good with approved material, including SS drain / grating with side perforation.	Nos.	3	1,500 4,500	1,200 3,600

SIGNATURE MEMBERS

Head - Fin Div. _____
 Head - Admin Div. _____
 Member-IDBL. _____
 Date: _____

S.No.	DESCRIPTION	UNIT	QTY	JAWED CONSTRUCTION COMPANY	G-A WOODS
5	Provide & fix approved quality chromium plated towel rails 750mm x 20mm (30" x 3/4") with brackets and C.P screws. (Taiwan make)	Nos.	2	2,500	2,500
6	Provide and fix approved quality C.P toilet paper holders and coat hook. (Taiwan make)	Nos.	2	3,000	2,500
7	Provide & fix p soap dish of approved quality with C.P screws. (Master /Sonex)(White color)	Nos.	2	3,000	2,500
8 (a)	Provide and fix Muslim Showers manufactured by Master/Sonex or equivalent, complete with stop cock and controlled spray head.(White color)	Nos.	2	7,500	7,500
(b)	Providing and fixing 15 mm dia C.P. mixer with C.P pipe 15 mm dia, of Master, Sonix or approved equal complete including pipe connections, all fittings, testing etc.(White color)				
i)	For Wash basin	Nos.	2	11,000	7,500
ii)	Kitchen Sink Mixer	Nos.	1	9,000	7,500
				22,000	15,000
				9,000	7,500

SIGNATURE MEMBERS PC-ADMIN

Head - Fin Div.

Head - Admin Div.

Member-DBL.

Date: _____