

	Bid Evaluation Report									
	Evaluation Report – Renovation of Shah Latif Town Branch Karachi – (0396)									
1	Name of Procuring Agency	Sindh Bank Ltd.								
2	Tender Reference No.	SNDB/COK/ADMIN/TD/1263/2022								
3	Tender Description	Renovation of Shah Latif Town Branch Karachi								
4	Method of Procurement	Single Stage One Envelope Bidding Procedure								
5	Tender Published / SPPRA S.No	T00531-22-0005. Express Tribune, Daily Express, Sindh Express (07/09/2022)								
6	Total Bid Documents Sold	01								
7	Total Bids Received	01								
8	Technical/Financial Bid Opening Date & Time	23/09/2022 at 1100 Hrs								
9	No. Of Bid qualified	01								
10	Bid(s) Rejected	00								

Detail on the above is as follows:-

S No	Nanæ of Firm or Bidder	Qualified / Disqualified in Technical / Eligibility Inspection	Cost offered by the Bidder	Ranking in terms of cost	Comparison with Engineering Estimated cost (Rs.3,524,850/-)	Reasons for acceptance/ rejection	Remarks
0	1	2	3	4	5	6	7
1.	M/s. R.R. Associate	Qualified	Rs.3,794,350/- (Area 1,350 pe sq.ft x Rate per sq.ft Rs.2,810.6296/-)	Only Bidder	Rs.269,500/- Above the estimated cost	Accepted as Only Qualified Evaluated Bid well within 15% limit	Rule 48 has been complied with

Accordingly, going by the Technical/Financial Evaluation criteria laid down in the tender document, M/s.R.R Associate is the most advantages bid i.e. Rs.3,794,350/-, hence recommended for Renovation of Shah Latif Town Branch.

Members Signature- Procurement Committee

Arshad Abbas Soomro Head of Administration

Dilshad Huusain Khan Chief Financial Officer

Syed Muhammad Aqeel Chief Manager, IDBL Karachi



TENDER No: SNDB/ADMIN/TD/1263/2022

Dated 29-09-2022

Branch Premises on Renovation of Shah Latif Town Branch Certificate in Compliance of Rule 48 of SPPRA

This is to certify that as only one bid was received against the tender, so Rule 48 has been complied with detail as follows:

S.No	Estimated Price	Current tender Price
01	Rs.3,524,850/-	Rs.3,794,350/-

Member Procurement Committee

Head of Admin Division

Head of Finance Division

Member of IDBL

MINUTES OF THE OPENING OF THE TENDER (TECHNICAL /FINANCIAL PHASE)

TYPE OF PROCUREMENT	ADMIN / IT / CONSULTANT / N	MEDIA	
TENDER NAME	Renovation at	Shah Letif Town	Br. KHI
TYPE OF TENDER	SINGLE STAGE-ONE ENVELOPE / SINGLE STAGE	-TWO ENVELOPE / TWO STAGE /TWO STAGE-TWO ENV	ELOPE
OPENING DATE	23-09.22		
OPENING TIME	1100 HVS!		
ATTENDANCE (MEMBER PC)			
78 M			
TEM			
(4.5)			
C.F	<u>NAME</u>	<u>FIRM</u>	BID OFFERED
ATTENDANCE (REPS. OF BIDDERS)	0.0		·
ATT .	R. R Associates.		3,794,350/-
ΥÆ		/	
* Com			
 			
TOTAL BIDS ACCEPTED FOR EVALUATION			
TO1, _ BIDS REJECTED			
ŖEMARKS			

SIGNATURE MEMBERS PC ADMIN
Head - Fin Div.
Head - Admin Div.
Member-IDBL.
Date:



ATTENDANCE SHEET BID OPENING -

FOR SELECTION OF Renevation of Shal Latif Town Brush KB2

Date: 23-09-2022

S.No	Company Name	Name of Company Representative	Contact No.	Company Address	Signature
01	Rf. Associates	Sy D	wp Bi	N	
			V		

Signature	-Procurement	Committee	Members /
		0011111111000	11101110010

Head of Administration

Chief Financial Officer

Chief Manager (IDBL)



RENOVATION OF SHAH LATIF TOWN **Evaluation Performa**

Serial No: 01

Bidder Name: RR-Associates

S. No.	Requisite	Total Points	Points Obtained	Point Criteria	Contractor Action (Documents to be enclosed)
1	Status of Firm	20		Private Limited/ Partner Ship	Certificate of incorporation/
1	Status of Firm	10	10	Sole proprietorship	Partnership deed/NTN
	Years in business	20	20	15 years and above	NTN Certificate / Letter of Incorporation /
2	(Only dealing with	15		10 years and above	Company Registration Letter is required to be enclosed or Declaration of
	financial institutions/Banks)	nks) 10		5 years and above	Commencement of Business with evidence is required to enclosed
	Branches up till now constructed/	40	уро	25 branches and above	Award letters to be attached duly issued from each financial institution's Admin Department that the contractor has
3	renovated for the Banks/Financial Institutions	30		15 branches and above	satisfactorily constructed the required number of branches for them. Complete Renovation work order will only be considered issued in last 15 years
	Average yearly	20	20	4 Million and above	Audited Financial Statements Report or
4	turnover in last three years	10		2 Million and above	Tax Return of last 3 years
	TOTAL POINTS	100	90	Qualifi	ied/Disqualified

Members Signatures- Evaluation Team

Athar Iqbal

Administration Division

Fouzia Shamim Operations Division

Taimoor Ghausi Finance Division

Members Procurement Committee

- HEAD OF ADMINISTRATION
- CHIEF FINANCIAL OFFICER
- 3 CHIEF MANAGER, IDBL

ignature

			MANDATORY / DISQUAL	IFICATION C	ONDITIONS			-
RENOVATION OF SHAH LATIF TOWN BRANCH KARACHI								
S.No	Contractors	Black Listing Affidavit (Yes/No)	FBR Registration/ Provincial Revenue Collecting Authority (Yes/No)	Alternate Bid Offered (Yes/No)	Tender Fee Submitted (Yes/No)	2 X Warning Letters issued by SNDB (Yes/No)	Blacklisted on SPPRA/Sindh Bank Ltd (Yes/No)	Qualified / DisQualified
1	R.R Associate	Yes	Yes	No -	Yes	No	No	Qualified
M.Atha Admin	ar Iqbal Fouz Division Opera	tia Shamim Taimoo ation Division Finance	or Ghausi e Division					
1. Arsh HEA 2. Dilsh CFO 3. Syed	ers Signature- Procurer nad Abbas Soomro D OF ADMINISTRATION nad Hussain d Muhammad Aqeel f Manager, IDBL	ment Committee	S.					



CERTIFICATE

This is to certify that no complaint has been received in related to Renovation of Shah Latif Town Branch Karachi having Reference No. SNDB/COK/ADMIN/TD/1263/2022 having SPPRA ID No: TOO531-22-0005.

Members – Procurement Committee

- 1) **HEAD OF ADMINISTRATION**
- 2) CHIEF FINANCIAL OFFICER
- CHIEF MANAGER, IDBL 3)

Signature

COMPARISON OF COST FOR RENOVATION WORKS- SHAH LATIF TOWN BRANCH KARACHI SINDH BANK LTD

		Engineering Estimated Cost	R.R. ASSOCIATE	DIFFERENCE	
S#	DESCRIPTION	AMOUNT	AMOUNT	AMOUNT	
Α	CIVIL WORKS	2,047,150	2,236,950	(189,800	
В	ELECTRIAL WORKS	1,078,700	1,054,900	23,800	
С	HVAC	209,000	202,500	6,500	
D	Removal &Installation of Existing items	190,000	300,000	(110,000)	
	TOTAL RENOVATION COST	3,524,850	3,794,350	(269,500)	

Head - Fin Div.

BILL OF QUANTITY Comparison of Cost of Renovation Works- Shah Latif Town Branch Karachi

S#	DESCRIPTION	LINUT			ering Estimate	RR. AS	SSOCIATES	DIFFERENCE
Α	CIVIL WORKS	UNIT	QTY.	RATE	AMOUNT	RATE	AMOUNT	AMOUNT
1	Termite Proofing							
	Providing and carrying out termite proofing using FIPROKILL/BIFLEX / DURSBANE with a solution of 1 gallon of chemical to 50 gallons of water, sparing this solution @ 2 liters per sq. meter area (or liters per 10.76 sft. Area) with a pressure ensuring at least 3" penetration in the soil of the area to be treated. The contractor will provide a guarantee for a period of ten years against infestation of termite in the shape and mode approved by the Engineer, stating that in case of infestation, additional treatment will by provided by the contractor at no extra cost to the Client (horizontal & Vertical).	SFT	1350	18	24,300	25	33,750	(9,45
2	REINFORCED CEMENT CONCRETE (Vault Room as per Layout Plan).				-		_	
	Providing and laying, compacting finishing & curing etc. straight or curved cast- in place designed mix 1:2:4 Reinforced Cement Concrete using 1 Part of Ordinary Portland Cement or equivalent, 2 Parts of silt free local sand and 4 Parts of 3/4" thick downgraded crushed stone; mixed in a manner to achieve a cube strength of 3000 psi in 28 days, including mixing, transporting, hoisting, lifting & placing at any height / depth, vibrating and curing etc. Complete in all respect including cost of Steel Reinforcement (3/8" dia steel bars G-60 @ 6" C/C both ways, staggered double jaal in a manner that the alternate spacing b/w bars should not increase 3" C/C) & form work for Cement Concrete including cutting, bending, laying in position, making joint and fastening, removal of rust from bars, cost of binding wire and labor charges for binding of steel reinforcement: also includes cost of form work and its removal. Complete in all respects, 9" thick walls, and column or as per direction of Engineer		230	900	Head		218,500	(11,50 C • ADMII

mer-inst...

S#	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT	RATE	AMOUNT	AMOUNT
3	Block / Brick Masonary works.					IXAIL	AWOUNT	AMOUNT
	Providing & laying Block / Brick masonary walls including racking of						-	
	joints with 1:4 cement sand mortar, the job includes Two 3/8" dia				> "			
	steel bars of 2'-0" length on both sides of wall at every 3'-0' ft height							
	for anchoring of masonry with the sides and Two 3/8 " dia bars of 2'-				-			
	0" length at every third block length for anchoring masonry walls to						-	
	plinth/floor beams, complete in all respect as per drawing,							
	specifications, to the satisfaction of Architect / bank's engineer.						, T	
	4" thick Block Masonary internal walls (First class Machine made Blocks)	SFT	600	160	96,000	200		
4	Plaster Works.				30,000	200	120,000	(24,000
	Providing & laying ³ / ₄ " thick cement sand plaster (Internal / External)			-			-	-
	with 1:4 cement sand mortar on walls, columns, beams, using best							
	quality O.P.C, including 6" inches wide mesh at joints of structure							
	with block masonary and over conduiting ,smooth trowel finish	CET	1000					
	complete in all respect. (This includes all the base plaster require for	SFT	1800	60	108,000	75	135,000	(27,000
	making diagonal and alignment for the exisiting walls) as per							
1	satisfaction of Architect / bank's engineer.						*	
5	Flooring, Elevation & Special Finishes.							
					-		-	-
	Providing and laying glazed full body Porcelain tiles 24" X 24" at							
	floor, of approved design, colour and pattern, china bone					2		
	colour or Master or equivalent full body porcelain, setting in							
	Stile dry bond (with cement), with matching color imported							
а	Grout. Complete in all respect, including curing, cleaning,	SFT	1350	380	513,000	480	648,000	(405.000
	finishing & hacking/chipping of existing surface for bonding					100	040,000	(135,000
	where necessary, and 4 inches wide skirting at walls of the same							
	tiles as above mentioned, with 1:2:4 PCC 50 mm thick, etc. as							
	per specifications and/or as directed by the Architect / Engineer (at any elevation)							
b	Tile Skirting 4" wide					CTCW.	VIII TO TO HADOS A	
~	The oxiting + wide	RFT	250	150	37,500	250	62 5hh	125.000

Sead - Admin DIV + range man Pomber - 1091, and an annual partners.

Datei

S#	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT	RATE	AMOUNT	AMOUNT
6	FALSE CELING					INAIL	AMOUNT	AMOUNT
	Gypsum Board (24"X24")				-			
	Providing & laying 8 mm thick gypsum board False Ceiling, 24" x 24" Elephant Brand or approved equivalent in straight, curved, tiles or multiple profiles, as shown on drawing section, fixed with imported powder coated, with groove, aluminum, " T" & "L" section with ceiling suspension system having provisions for light and AC grill. Complete in all respect as per drawing and instruction of Bank's Engineer.	SFT	1350	135	182,250	140	189,000	(6,750
7	Marble				-		_	
	Providing & fixing pre polished 3/4" thick Marble Top quality							
3	with approved size and shade over 2" thick pre cast RCC slab							
	including 1/2" thick gola, grouting and jointing including cost of							
	cutting of marble for basin and sink bowl including filling with				-		-	
	silicone around joint of marble complete in all respect as per							
	satisfication by the engineer.							
	Pantry Counter Top (Boticina)	SFT	20	600	12,000	650	13 000	(4.00)
					12,000	000	13,000	(1,000

SIGNATURE MEMBERS CADMIN
Head - Fin Div.
Head - Admin Div.
Member-TDBL

S#	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT	RATE	AMOUNT	AMOUNT
8	WOODEN CABINETS				-		AMOUNT	ANIOUNI
	Kitchen Cabinets				-			
a	Lower Unit: Providing, fabricating and fixing in position pantry cabinets 24" deep 32" high consisting of 3/4" thick laminated board (Furniture color) of SONEX, Noor or equivalent on front shutter and drawers, Dark grey on internal box and shelves moulding 1/2"x3/4" including nails, screws, bolts, imported hinges, catchers, locks, handles, 3 coat of sprit polish of matching shade of furniture color on wood lipping and wood preservative treatment including premium quality ceramic tiles above 4" thick P.C.C floor platform complete in all respects as per drawings and as directed by the bank's Engineer. all kind of best quality hardware's, spring hinges, SS handles, locks etc. Complete in all respects.	SFT	18	1250	22,500	1500	27,000	(4,500
b	Upper Unit: Providing, fabricating and fixing in position pantry cabinets 12" deep and 24" high (Hanging) consisting of 3/4" thick laminated board (Furniture color) of SONEX, AL Noor or equivalent on front shutter and drawers, Dark grey on internal box and shelves moulding 1/2"x3/4" including nails, screws, bolts, imported hinges, catchers, locks, handles, 03 coat of sprit polish of matching shade of furniture color on wood lipping and wood preservative treatment complete in all respects as per drawings and as directed by the bank's Engineer.	SFT	20	1350	27,000	1500	30,000	(3,000

SIGNATURE PENDAND M. ADMIN
Head - Fin Div.
Head - Admin Div.
Wender-1081

S#	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT	RATE	AMOUNT	AMOUNT
9	Paint at Walls				-		AMOUNT	AWOUNT
	Providing and applying, 3 coats of ICI Matt Finish Paint Ash White (3130) or BERGER or equivalent of approved colour and shade, at any floor & at any height over one coat of primer and making smooth and even surface by appling ICI Paintex base filling as per specifications, to surface of walls, complete in all respects as specified and as approved by the bank's Engineer.	SFT	2600	60	156,000	65	169,000	(13,000
10	WOODEN DOOR / FRAME / CHOWKAT /Beading				_			
а	DOOR FRAME: Providing and fixing of required width, 16 SWG, GI door frames for Toilets, kitchen, stores & cash counter with polishing, including Lintels, hold fasts, where ever required, complete in all respect including painting / polish with proper beach / diyar wood beading.		4	7000	28,000	7000	28,000	-
b	SKIN DOORS, 1-1/2 inches thick (for Toilets, Kitchen, stores & cash counter) Provide and install doors consisting of best quality Malaysian skin, pressed over best quality treated partial wood framing, with approved quality of door locks, handle, tower bolt, hold fast, stopper, hardware and paint /polish, complete in all respect.	SFT	84	600	50,400	600	50,400	-
11	Wooden Hanging Beams.							
	Providing & fixing in postion wooden Beams for support to fix glass and glass door consitsting of 1 1/2 x3" @ 2'-0" c/c partal wood framing and 1/2" MDF Lasani board (Malaysia) on both sides including nails, bolts, glue wastage, wood preservative, treatment & 3 coats of paint complete in all respect as per drawings and as directed by Bank's Engineers.	-	30	650	19,500	1350	40,500	(21,000)
12	INSTALLATION OF VAULT ROOM DOOR							
	Lifting & Fixing charges of Bank's supplied Vault / Locker Doors, welding of door frame with RCC MS bars, and to facilitate the Vendors. Complete in all respects.	NO	1	15000	15,000	2000	TURE 1/2/000/1	13,000

MEMBER I SOURCE CONTRACTOR CONTRA

5 of 7

S#	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT	RATE	AMOUNT	ANIOUNT
13	GLASS DOOR (BM Cabin, ATM front)				-	IVAIL	AWOUNT	AMOUNT
3	Providing, fabrication & fixing 12 mm thick glass door with top & bottom locking system, 4" Aluminum D-48 by Lucky or equivalent section, with 12mm thick Middle East / Saudi Arabia or equivalent clear glass with frost film and Bank's monogram, Approved Ajrak film, with gasket size and shape as shown on drawing, including bolts, D lock, nuts, screws aluminum channel, handle, floor machine (New Star or equivalent), locks etc. Complete in all respects as directed by Engineer.	SET	63	1650	103,950	1350	85,050	18,90
14	GLASS PARTITION				-		-	
	Providing and installation 12mm thick glass KSA/UAEor equivalent polished glass with 100mm top & bottom rails, brush finish SS-304, lucky or equivalent section with frosted film surface as per approved design. Contractor is required to provide joints between the panels with minimum 5mm thick clear silicon from Dow corning or other approved by the Engineer. Complete in all respects.	SFT	100	950	95,000	950	95,000	
15	MARBLE AT ENTRANCE/Stair STEPS							
	Providing and laying 20mm thick Marble of approved quality and size on any type of flooring straight or curved, as per drawings, laid with cement slurry over cement sand mortar (1:4), including filling of joint with grouting material, rubbing, rounding and final chemical polish etc, complete in all respects.		180	600	108,000	550	99,000	9,000

SIGNATURE MENGERS PC-ADMIN
Head Fin Div.
Head - Admin Div.
Member-1081.
03'0

S# ·	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT	DATE	AMOUNT	
16	Wrought Iron Grills for external windows, AC outers (If nece	ssarv)		INAIL	ANOUNT	RATE	AMOUNT	AMOUNT
	Approved design grills for all external windows & Ac Outers/exhaust fans (if required). The security grills will be installed from inside so that glass will be visible from outside. MS Grill comprising of 1/2" solid square bars @ 6" c/c 1"x1-1/2" MS 16 gauge angle iron, welding, grinding, finishing, rubbing 3 coat of enamel paint (ICI,NIPPON,BERGER or equivalent) red oxide before paint. Complete in all respects, as per standardized design and /or as shown in drawing as per approved design, attached herewith. Further proper lockable grills with above specification will also be provided for all AC outdoor units.	SFT	170	650	110,500	550	93,500	17,000
17	ATM ACCESS RAMP FOR DISABLED PERSON				-			,
	A three feet wide CC ramp, at 30 degree, will be provided for disabled person. The ramp tiles will be grooved tiles and, SS railing will be provided Cost includes all said material, complete in all respect.	No	1	35000	35,000	35000	35,000	-
	Pvers at Front with P.C.C	Sft	100	250	25,000	200		
				200	23,000	200	20,000	5,000
17	M.S DOOR on Emergency exit, ATM internal & Guard Post				-		-	_
	Fahricating providing and fiving MS door with 40 0 M 0 M 0				-		-	-
,	Fabricating, providing and fixing MS door with 16 S.W.G M.S 3/4" square pipe, 16 SWG MS sheet pressed over this frame including metal door frame, at both sides, sheet frame painted with approved enamel color including 2" x 5" eye level opening with proper MS shutter of 16 swg sheet to look outside, including best quality hinges, locks, handles, hold fasts and other necessary hardware etc. size as per site. Complete in all respects as per drawing attached herewith, specifications and as directed by the Bank.	SFT	57	1250	71,250	750	42,750	28,500
	TOTAL CIVIL WORK	S			2,047,150		2 226 050	400 5
				an Star Bay at Sold	_,0 +1 ,100		2,236,950	(189,800)

SIGNATURE MANDERS PC-ADMIN
Head - Fin Div.
Head - Admin Div.
Member-IDBL.

CNI				Engineer	ing Estimate	RR. ASS	SOCIATES	Differen	ice
S.No.	DESCRIPTION NTERNAL WIRING	UNIT	QTY	Rate	Amount	Rate	Amount	Differen	icc
	Supply, installation and commissioning of Light Circuit wiring, from MCB in DB to Switch Board to be wired with 3x2.5mm sq. (P+N+PE) PVC insulated 300/500 V grade wire, manufactured by M/s. "AGE, Pioneer, FASTor equivalent, or as specified in Annexure A, in and including cost of 1" dia. heavy duty PVC conduit make Popular, Beta, installed on roof slab, above false ceiling, or concealed in walls, or as required as per site conditions, all PVC conduit accessories, pull boxes, steel pull wires, Complete in all respects. Each circuit shall have independent CPC. Maximum wiring of 2 light circuits can be pulled through 1" dia. PVC conduit.								,
	3	Nos.	6	4500	27,000	4000	24,000		3,00
2	Providing, Installation, testing and commissioning of wiring of One light point controlled by one switch and wired with 3x1.5 mm sq. PVC insulated wires 300/500 V grade, in and including cost of 3/4" dia. heavy duty PVC conduit recessed in wall, columns slabs or above light carrier all PVC conduit accessories, 3" high PVC junction boxes, pull boxes, steel pull wires, PVC flexible conduit from ceiling junction box to light fixture with brass chuck nut including cost of 3x1.5mm sq from Ceiling Junction Box to Light Fixture, M.S. sheet steel switch box 16 SWG with earth terminal and 2 coats of enameled paint, M.S. box shall be of the same size as that of 1, 2 or 3 gang flush type plate switches, including cost of gang type light switches 10 amps.				Head - Fir Head - Ad Member-)	min Div.		THE REPORT OF THE PARTY OF THE	_
		Nos.	4	3500	14,000	3000	12,000		2,00
					-		_		;

S.No.	DESCRIPTION	UNIT	QTY	Rate	Amount	D .		
3	Providing, Installation, testing and commissioning of wiring of Two light points controlled by one switch and wired with 3x1.5 mm sq. PVC insulated wires 300/500 V grade, in and including cost of 3/4" dia. heavy duty PVC conduit recessed in wall, columns slabs or above light carrier all PVC conduit accessories, 3" high PVC junction boxes, pull boxes, steel pull wires, PVC flexible conduit from ceiling junction box to light fixture with brass chuck nut including cost of 3x1.5mm sq from Ceiling Junction Box to Light Fixture, M.S. sheet steel switch box 16 SWG with earth terminal and 2 coats of enameled paint, M.S. box shall be of the same size as that of 1, 2 or 3 gang flush type plate switches, including cost of gang type light switches 10 amps.			Hate	Amount	Rate	Amount	;
	3	Nos.	10	3800	38,000	4500	45,000	(7,000)
4	Providing, Installation, testing and commissioning of wiring of Three				~		/-	- (7,000)
	light points controlled by one switch and wired with 3x1.5 mm sq. PVC insulated wires 300/500 V grade, in and including cost of 3/4" dia. heavy duty PVC conduit recessed in wall, columns slabs or above light carrier all PVC conduit accessories, 3" high PVC junction boxes, pull boxes, steel pull wires, PVC flexible conduit from ceiling junction box to light fixture with brass chuck nut including cost of 3x1.5mm sq from Ceiling Junction Box to Light Fixture, M.S. sheet steel switch box 16 SWG with earth terminal and 2 coats of enameled paint, M.S. box shall be of the same size as that of 1, 2 or 3 gang flush type plate switches, including cost of gang type light switches 10 amps.			Hear	NATURE W - Fin Div	// II		
						×		
		Nos.	15	4000	60,000	4500	67,500	(7,500)
	Same as Item No. A.02 mentioned above, but wiring of Wall Bracket Fan points including cost of M.S sheet steel switch box 16 SWG with earth terminal 1-10 Amps gang type switch make CLIPSAL (Australia), PDL (New Zealand), ABB (Italy), MK (UK), Legrand (France).				-		_	-
	•	Nos.	2					

S.No.	DESCRIPTION	UNIT	QTY	Rate	Amount	D		
				Rate	Amount	Rate	Amount	
6	Confirming to same specifications as mentioned above in Item No. A.02 but wiring of Exhaust Fan points, including cost of hook box and cost of 10 Amp switch make Clipsal M.S box 16 SWG with earth terminal, 2 coats of antirust point, all fixing accessories, 1-5 Amps ceiling rose and including one switch of 10 amps switch, make CLIPSAL (Australia), PDL (New Zealand), ABB (Italy), MK (UK), Legrand (France)	No.	3	2500	7,500	3500	10,500	(3.000
7	Providing & wiring of 1-3 pin 15 Amps power socket outlets (for General Use) wired with 2x4mm2+1x2.5mm² CU/PVC insulated cable 300/500 Volt grade, make Pakistan cables, Fast, Pioneer in 25mm dia PVC conduit make Beta, Popular, recessed in wall/floor, above false ceiling or as required as per site conditions, all PVC conduit make Beta accessories, pull boxes, steel pull wires. Complete with all conduit & wiring accessories including 15 Amps, 3 pin combined switch socket make Clipsal (Austria), Panduit ,MK(UK), Legrand (France) or approved equivalent. Wiring shall be done directly from the MCB installed in the respective DB without any claim of circuit. complete with suitable size 1.5mm thick sheet steel back box recessed in wall.				_		-	(3,000
		Nos.	4	5500	22,000	5000	20,000	2,000
	Providing & wiring of 1-3 pin 10 Amps power switch socket outlets (for RAW supply / WAPDA) wired with 3x2.5mm2 1 core CU/PVC insulated cable in 25mm dia PVC conduit make Beta, Popular, recessed in wall/floor, above false ceiling or as required as per site conditions, all PVC conduit make Beta accessories, pull boxes, steel pull wiresetc. Complete will all conduit & wiring accessories including 10 Amps, 3 pin combined switch socket make Clipsal (Austria), MK(UK), Legrand (France) or approved equivalent. Wiring shall be done directly from the MCB installed in the respective DB without any claim of circuit complete with suitable size 1.5mm thick sheet steel back box recessed in wall.			and the second s	GNATURE ad-Fin Div. ad-Admin I amber-IDBL Date:	Displace of the second		;
		Nos.	5	5000	25,000	5000	25,000	_

.No.	DESCRIPTION	UNIT	QTY	Rate	Amount	Rate	Amount	
i)	Confirming to some specification				-		Amount	7
1)	Confirming to same specification as mentioned above in item A-08, but outlet to outlet wiring. Complete in all respect.	Nos.	6	3000	18,000	500		-
					-	300	3,000	15,00
9	Providing & wiring of 2-3 pin 13 Amps power switch socket outlets (for UPS) wired with 3x2.5mm2 1 core CU/PVC insulated cable in 25mm dia PVC conduit make Beta, Popular, recessed in wall/floor, above false ceiling or as required as per site conditions, all PVC conduit make Beta accessories, pull boxes, steel pull wires. Complete will all conduit & wiring accessories including 13 Amps, 2/3 pins combined switch socket (duplex) make Clipsal (Austria), MK(UK), Legrand (France) or approved equivalent. Wiring shall be done directly from the MCB installed in the respective DB without any claim of circuit. complete with suitable size 1.5mm thick sheet steel back box recessed in wall.						-	
		Nos.	5	5000	25,000	5000	25,000	-
i)	Confirming to same specification as mentioned above in item A-09, but outlet to outlet wiring. Complete in all respect.	Nos.	6	3000	18,000	5000	30,000	- (10.00
	Providing installing & wiring for Split A/C's unit from distribution board to respective 1-3 pin 16 Amps switch socket, wired with 2x6mm² + 1x4mm² 1 core CU/PVC cable in 25mm dia PVC conduit make Beta, Popular, recessed in wall/floor, above false ceiling or as required as per site conditions, all PVC conduit make Beta accessories, pull boxes, steel pull wiresetc. Complete will all conduit & wiring accessories including 16 Amps, 3 pin combined switch socket make Clipsal (Austria), MK(UK), Legrand (France) or approved equivalent. Wiring shall be done directly from the MCB installed in the respective DB without any claim of circuit. complete with suitable size 1.5mm thick sheet steel back box recessed in wall. Ccomplete with all accessories including termination.			Hai	GNATURE 1 ad - Fin Div id - Admin Div nber-IDBL Date:	and		(12,000
		Nos.	5	8500	42,500	9000	45,000	(2,500
		4 of 10			_	'A	-	

S.No.	DESCRIPTION	UNIT	QTY	Rate	Amount	Rate	A	
i)	Confirming to same specifications & wiring, as mentioned above in Item No. A.10 but wiring for Signboards from distribution board to 1-3 pin 20 Amps MCB	No.	1	8500	8,500	9000	9,000	(500)
11	Providing, Installation, testing & commissioning of light fixtures & other accessories, complete with all accessories such as, Chain, Rod, Screw, foundation for garden light etc. Complete in all respect with chokes (ballast), lamp holders, starters, power factor correction capacitor, tube rods internal wiring, earthing terminal.				-		-	-
i)	Flat Panel LED OS-DL3-12W (round) of Osaka or equivalent 6" dia	Nos.	65	1450	94,250	1450	94,250	
12	Supply, installation and commissioning of Exhaust / Bracket Fans of following sizes, plastic body, louvers, all necessary fixing accessories, make Asia, Climax, National or as manufactured by any one of the manufacturers as mentioned in Annexure-"A". Complete in all respects.				-		-	:
i)	Exhaust Fan 12" dia	Nos.	3	5500	16,500	4000	-	_
ii)	Wall Bracket Fan 24" dia	Nos.	2	6500	13,000	4000 8000	12,000	4,500
					-		-	(3,000)

Member 108 Li announcement de la constant de la con

.No.	DESCRIPTION	UNIT	QTY	Rate	Amount	Rate	Amount	
	MAIN SWITCHES AND DBs (General Specifications)				-	Rate	Amount	
	All concealed with 16 SWG MS powdered coated box for DBs and 18 SWG MS sheet box for outside 100 Amps, TP breaker, with door, hinges, lock, Amps meter, Volt meters, selector switches, LED indicating lamps, earth strips with 10 holes, neutral strips with 12 holes, backed powdered coating, water proof gasket, The work include all internal wiring with / 99.995 copper busbars, proper sized above mentioned approved PVC wires, at all DBs from TP breakers / Switches with standard copper termination of each breakers at all phases., wiring for volts /Amps meters, selectors, indicators etc., thus complete DB in all respect with DB body earthing with earth wire. All breakers in all DBs will be Japanese Brand, Terasaki, Clipsal; MG, Schneider, Legrand. or equivalent							
							-	2
13	Out Side Breaker / Switch at incoming line	No.	1	25,000,00	-		-	
	, and an another state of the s	140.	1	25,000.00	25,000	20,000.00	20,000	5,000
14	MAIN DB, Raw power, AC and power sockets with Emergency po	wer			-		-	-
	Providing, Installation, testing and commissioning of Lighting & Power Distribution Board (L+P. DB) of 1.5mm thick sheet steel fabricated concealed type as per site condition suitable for 3-phase, 4 wire, 50 Hz, A/C system as per following configuration.(All electrical components to be selected from approved manufacturer's list and DB's from approved vendors only)				-			-
						TALATI	20 00 1 0 1 0 1 0 0 0 0 0 0 0 0 0 0 0 0	10000
	INCOMING				- 6	- a. a. 1 0 3 8 8 4 1	1 2 2 8 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	
	1-100 Amps TP, 25 KA, MCCB.					lead-Fin þ	in plant	
	3-Phase indication lamps. with fuse				-	tand Admi	J- Jan	-
	1-Voltmeter Digital 0-500 volts with selector switch.				- 5	load - Admi	H W V . Danger	1
	1-Amps. Meter Digital with selector switch.				-	Agminu-Id		<u> </u>
	1-Neutral bar.					196. 7	- 1	
	1-Earth bar.				-	10016	F SERVER CONTRACTOR PRODUCTION AND ADMINISTRATION OF THE PROPERTY OF THE PROPE	_ 1

S.No.		UNIT	QTY	Rate	Amount	Rate	Amount	
	OUTGOING :				_	Tate	Amount	
	12-10 Amps S.P, 6 KA, MCBs						-	-
	6-16 Amps S.P, 6 KA, MCBs	Nos.	1	95,000.00	95,000	70,000.00	70,000	
	12- 20 Amps TP, 10 KA, MCB			,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	75,000	70,000.00	70,000	25,000
	1-32 Amp TP,10 KA MCB						-	
					-		-	***
					-		-	-
15	UPS DB				-		-	-
	This DB will also be same specification but consist of one SP, two pole incoming breaker and 6, 10 Amps and 3, 15 Amps breakers and one two pole 15 Amps breaker for ATM. With 3x4mm wires till ATM power socket.	Nos.	1	65000	45.000		-	;
		1403.	1	63000	65,000	50000	50,000	15,000
16	Providing, Installation, testing and commissioning of 32A Singel Phase 3 Pin Industrial Sockets in M.s box for UPS incoming and outgoing cables for IT.	Nos.	2	5,500.00	11,000	5,000.00	10,000	1,000
17. L.	T POWER CABLES				_		-	_
	Providing, laying, testing and commissioning of following size single or multicore PVC/PVC cable 600/1000 volts grades, manufacturted by Pakistan Cables, AGE, Pioneer, in suitable PVC conduit concealed in floor / wall as shown on drawings, and as per instruction of Consultant.				-		-	-
ii)	25mm² 4core cu/pvc/pvc cable from main connection to Main DB	Mtrs.			-		-	-
	10 24		30	3000	90,000	3500	105,000	(15.000)
	10mm ² 4core cu/pvc/pvc cable Main DB to UPS DB & looping	Mtrs.			,	3300	103,000	(15,000)
iii)			25	1150	28,750	1300	32,500	(2.750)
iv)	6mm² 4core cu/pvc/pvc cable + 2x4mm² 1core cu/pvc cable	Mtrs.	25	750	18,750	14 8000 E N	E 800 2 1 10 0000000000000000000000000000	(3,750) (1,250)

Head - Fin Div.

Mambar-Yhai

Date:

S.No.		UNIT	QTY	Rate	Amount	Rate	Amount	
18. T	ELEPHONE SYSTEM				_	Title	7 mount	
i	Providing & wiring of each Telephone socket outlet in preinstalled outlet boxes, wired with 4 Pair Cat-6 (UTP)Cable, make 3M / PANDUIT USA in 25mm dia PVC conduit recessed in slabs, floors, walls, columns or on slab above false ceiling or as required as per site conditions,, complete with all conduit & wiring accessories including RJ-45 IOs & Face Plates. Complete in all respect with suitable size 1.5mm thick sheet steel back box recessed in wall.						-	- - - - -
		Nos.	7	6500	45,500	6000	42,000	3,500
ii	Providing, laying testing and commissioning of 20 Pairs Telephone Cable, of Siemens, in 32mm dia pvc class-d pipe	Mtrs.	25	550.00	13,750	850.00	21,250	(7,500)
iii	Providing & fixing 30 Pairs Telephone Tag Block (MDF) enclosed in 1.5mm thick sheet steel box with all fixing accessories.				-		-	-
19 C	OMPUTER NET WORKING SYSTEM	No.	1	15,000.00	15,000	20,000.00	20,000	(5,000)
17. 0	Providing, laying & testing of Data Cable 4 Pair Cat -6, make 3M / PANDUIT USA in 25 mm dia PVC conduit including Data Outlet (3M make) Face plate (2port) w/o shutter RJ-45 (Panduit USA)K6 Jack fixed, on 1.5 mm thick steel back box complete in all respect and as per darwing. and providing of Fluke Test Report & 3M's 20 Years Certificate (Complete as per Client's requirement)	2			-		-	-
i		Nos.	7	6500	45,500	6000	42,000	3,500

ISNATURE NEW DE CADMIN
Head - Fin Div.

S.No.	DESCRIPTION	UNIT	QTY	Rate	Amount	Rate	Amount	
					-		_	
ii	24 Ports Cat-6 Patch Panel, make 3M	No.	1	25,000.00	25,000	30,000.00	30,000	(5,000)
iii	"Owner provided" Managed Switch 24 Ports 1.0 Gbps (Linksys by Cisco)				-		-	-
							-	
iv	Supply of machine made 3M Cat-6 Patch Cable (1m) with both end				-			_
	connectors	Nos.	7	750.00	5,250	850.00	5,950	(700)
					-		-	
V	Supply of machine made 3M Cat-6 Drop Cable (3m) with both end connectors	Nos.	7	850.00	5,950	850.00	5,950	
						00000	3,730	_
vi	Supply at site, installation and commissioning of best quality Communication Rack / Data Cabinet in IT Room, of any of the following size, made of M.S sheet, powder coated, having lockable glass door at front, exhaust fans on top, suitable for patch panels of required voice and data points, to be terminated on modular patch panel, including cost of power extension board, and termination. Complete in all respect.						_	_
vii	27 U	No.	1	25,000,00	-		-	
-		140.	1	35,000.00	35,000	35,000.00	35,000	_


Providing, installation, commissioning and testing of TWO earthing pits (40 to 50 ft deep or up to water level), back filling, ramming etc. complete with copper earth electrode 25mm dia and 1.5 meter long, as indicated in specification and drawings. 16 mm copper wire from electrode to ECP and to all DBs. Complete with cable clamps 38mm dia G.I. pipe till electrod from ECP, with "T", plug, for water refilling and all accessories as per drawings. Each earth pit is to be provided with a concrete manhole 300 x 300 x 450(mm) deep with 225mm thick wall including cement mortar, internal plaster 1:4, with heavy duty C.I. cover including test clamp. Complete in all respect. Earthing bores shall be made at 6 to 8 feet away from foundation and distance between earth pits shall not be less than 10 feet. Further connection of earth pit to all DBs with proper earth wire. In case where earth bore is not possible, due to hilly area, copper plate earth, having size 2'X2'X1/4", with two 10 SWG 16 mm copper wires, tight on plates with brass nut / bolt, plate buried in 6 to 8 feet deep in earth will be provided with UPVC pipe for water refilling fro ground level till earth plate.	No.	DESCRIPTION	UNIT	QTY	Rate	Amount	Rate	A	
pits (40 to 50 ft deep or up to water level), back filling, ramming etc. complete with copper earth electrode 25mm dia and 1.5 meter long, as indicated in specification and drawings. 16 mm copper wire from electrode to ECP and to all DBs. Complete with cable clamps 38mm dia G.I. pipe till electrod from ECP, with "T", plug, for water refilling and all accessories as per drawings. Each earth pit is to be provided with a concrete manhole 300 x 300 x 450(mm) deep with 225mm thick wall including cement mortar, internal plaster 1:4, with heavy duty C.I. cover including test clamp. Complete in all respect. Earthing bores shall be made at 6 to 8 feet away from foundation and distance between earth pits shall not be less than 10 feet. Further connection of earth pit to all DBs with proper earth wire. In case where earth bore is not possible, due to hilly area, copper plate earth, having size 2'X2'X1/4", with two 10 SWG 16 mm copper wires, tight on plates with brass nut / bolt, plate buried in 6 to 8 feet deep in earth will be provided with UPVC pipe for water refilling fro ground level till earth plate. Nos 2 60000 120,000 50000 100,000 20,000 Total - Electrical works	. E.	ARTHING SYSTEM				mount	Rate	Amount	-
Total - Electrical works 20,000 1078 70		Providing, installation, commissioning and testing of TWO earthing pits (40 to 50 ft deep or up to water level), back filling, ramming etc. complete with copper earth electrode 25mm dia and 1.5 meter long, as indicated in specification and drawings. 16 mm copper wire from electrode to ECP and to all DBs. Complete with cable clamps 38mm dia G.I. pipe till electrod from ECP, with "T", plug, for water refilling and all accessories as per drawings. Each earth pit is to be provided with a concrete manhole 300 x 300 x 450(mm) deep with 225mm thick wall including cement mortar, internal plaster 1:4, with heavy duty C.I. cover including test clamp. Complete in all respect. Earthing bores shall be made at 6 to 8 feet away from foundation and distance between earth pits shall not be less than 10 feet. Further connection of earth pit to all DBs with proper earth wire. In case where earth bore is not possible, due to hilly area, copper plate earth, having size 2'X2'X1/4", with two 10 SWG 16 mm copper wires, tight on plates with brass nut / bolt, plate buried in 6 to 8 feet deep in earth will be provided with	Nos	2	60000	120,000	50000	100.000	
1079 700					30000	120,000	30000	100,000	20,000
		Total - Electrical works				1 079 700		-	_

SIGNATURE PROPERTY AND STREET OF THE STREET

AIRCONDITIONING / HVAC WORKS:

		enganian in Industria		Enginee	ring Estimate	RR. ASSOCIATES			
S# ,	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT	RATE	AMOUNT	DIFFERENCE	
1	Installation of Split Air Conditioners (SAC)		ANTO STATE OF THE PROPERTY.						
	a) 1.0 Ton SAC	Nos	-	5,500	-				
	b) 1.5 Ton SAC	Nos	-	5,500	_			_	
	c) 2.0 Ton SAC	Nos	-	,				-	
2	Estimate additional copper piping with insulation for split units make(Muller)including control wiring from outdoor unit to indoor with 2 x 1.5 mm.sq. + 1 x 1.5 mm.sq wire drawn in PVC 'D' class conduit clipped to wall or ceiling (wiring make Pakistan Cable, AGE or Pioneer). The return and supply copper tubing to be sized as per manufacturer's recommendation and to be drawn in separate Aeroflex (charged as per final measurement on site). The return and supply copper tubing to be sized as per manufacturer's recommendation and to be drawn in separate Aeroflex insulators with gray tape.	rft	300	500		500	J. 150000		
3	Provide & fix UPVC, 1-1/4" dia and 1" dia pipe, Beta or popular, for AC drain system, (medium) conforming to BSS 1307 of 1957, along with PVC fittings such as tees, elbows, unions, reducers, sockets, Teflon tape for jointing, hangers, supports, sleeves, including testing and commissioning and insulation with Aero flex insulation.		250	180	45,000	150	37,500	7,500	
					-		-	-	
4	Providing and installing M.S angle iron brackets, treated with rust	Set	5	2,800	14,000	3,000	15,000	- 1,000	
	TOTAL CIVIL WORK	(S			209,000		202,500	6,500	

	D. COST OF UTILIZATION OF EXISTING ITEMS (Following items from Bahira Complex II branch	Removal, shifting & installation of https://doi.org/10.1001/10		
S#	Items		Engine i = 4	
1	Glass Doors (Main ATM Entrance,BM Cabin) job includes new floor machines	2 Nos (Cost includes new floor machines)	Engineering Estimate	RR. ASSOCIATES
2	Glass Partition	120 sft		
3	All wooden Furniture (Chairs+tables+Cash Counters)	1 job	,	
4	All Steel Items (Vault Room Door, Safe+SS Card Trolley+Fire Almrah)	1 job Complete in allrespect)	190,000	300,000
5	ACs	5 (Gas charges, sevice)		



4 FINANCIAL PROPOSAL


PRICE SCHEDULE

(Applicable for the year 2022-23)

Name of Bidder

	ESTIMATE FOR RENOVATION WORKS- SHAH LATIF TOWN BRANCH KARACHI SINDH BANK LTD						
S#	DESCRIPTION	Area 1350 sft AMOUNT					
Α	CIVIL WORKS	2236950 -					
В	ELECTRIAL WORKS	1054900 -					
С	HVAC	202500-					
D	Removal &Installation of Existing items	300,000.					
	*TOTAL RENOVATION COST	3794350-					

^{*}This amount will be considered as only the "Bid Offered". Whereas be apprised that the successful bidder will be the one hose "Evaluated Bid" is the lowest. (For further clarification refer Note 9. below)



SIGNATURE MINDING PC-ADMIN
Head - Fin Div.
Head - Admin Div.
Member-IDDL:
Date:

BILL OF QUANTITY Renoavtion Works- Shah Latif Town Branch Karachi

S#	DESCRIPTION	LIAUT	OTV	DATE	
Α	CIVIL WORKS	UNIT	QTY.	RATE	AMOUNT
1	Termite Proofing	-	-	-	-
	Providing and carrying out termite proofing using FIPROKILL/ BIFLEX / DURSBANE with a solution of 1 gallon of chemical to 50 gallons of water, sparing this solution @ 2 liters per sq. meter area (or liters per 10.76 sft. Area) with a pressure ensuring at least 3" penetration in the soil of the area to be treated. The contractor will provide a guarantee for a period of ten years against infestation of termite in the shape and mode approved by the Engineer, stating that in case of infestation, additional treatment will by provided by the contractor at no extra cost to the Client (horizontal & Vertical).	SFT	1350	25	33750 -
2	REINFORCED CEMENT CONCRETE (Vault Room as per Layout Plan).				
)	Providing and laying, compacting finishing & curing etc. straight or curved cast- in place designed mix 1:2:4 Reinforced Cement Concrete using 1 Part of Ordinary Portland Cement or equivalent, 2 Parts of silt free local sand and 4 Parts of 3/4" thick downgraded crushed stone; mixed in a manner to achieve a cube strength of 3000 psi in 28 days, including mixing, transporting, hoisting, lifting & placing at any height / depth, vibrating and curing etc. Complete in all respect including cost of Steel Reinforcement (3/8" dia steel bars G-60 @ 6" C/C both ways, staggered double jaal in a manner that the alternate spacing b/w bars should not increase 3" C/C) & form work for Cement Concrete including cutting, bending, laying in position, making joint and fastening, removal of rust from bars, cost of binding wire and labor charges for binding of steel reinforcement: also includes cost of form work and its removal: Complete in all respects, 9" thick walls, and column or as per direction of Engineer	CFT	The state of the s	950	21850 -
3	Block / Brick Masonary works.	. Arimir	1017.	/ Sr	
\		54 27 1 2 3 1 1 2	2	1	2)
	Providing & laying Block / Brick masonary walls including racking of joints with 1:4 cement sand mortar, the job includes Two 3/8" dia steel bars of 2'-0" length on both sides of wall at every 3'-0' ft height for anchoring of masonry with the sides and Two 3/8" dia bars of 2'-0" length at every third block length for anchoring masonry walls to plinth/floor beams, complete in all respect as per drawing, specifications, to the satisfaction of Architect / banks, engineer. 4" thick Block Masonary internal walls (First class Machine made Blocks)	er-100 Date	600	2,000	120000
A	() / \	//			
4	Plaster Works.				


5	Providing & laying ³ / ₄ " thick cement sand plaster (Internal / External) with 1:4 cement sand mortar on walls, columns, beams, using best quality O.P.C, including 6" inches wide mesh at joints of structure with block masonary and over conduiting ,smooth trowel finish complete in all respect. (This includes all the base plaster require for making diagonal and alignment for the exisiting walls) as per satisfaction of Architect / bank's engineer. Flooring, Elevation & Special Finishes.	SFT	1800	75	135000
a	Providing and laying glazed full body Porcelain tiles 24" X 24" at floor, of approved design, colour and pattern, china bone colour or Master or equivalent full body porcelain, setting in Stile dry bond (with cement), with matching color imported Grout. Complete in all respect, including curing, cleaning, finishing & hacking/chipping of existing surface for bonding where necessary, and 4 inches wide skirting at walls of the same tiles as above mentioned, with 1:2:4 PCC 50 mm thick, etc. as per specifications and/or as directed by the Architect / Engineer (at any elevation)	SFT	1350	480	648.000-
b	Tile Skirting 4" wide	RFT	250	200	62500 -
6	FALSE CELING				
7	Providing & laying 8 mm thick gypsum board False Ceiling, 24" x 24" Elephant Brand or approved equivalent in straight, curved, tiles or multiple profiles, as shown on drawing section, fixed with imported powder coated, with groove, aluminum, "T" & "L" section with ceiling suspension system having provisions for light and AC grill. Complete in all respect as per drawing and instruction of Bank's Engineer. Marble	SFT		140	189 000 - SPC-ADMIN
	Warble	Admi	1 Div	1/8	9/
	Nem's	er-IDI	in a castraction of	1	8
	Providing & fixing pre polished 3/4" thick Marble Top quality with approved size and shade over 2" thick pre cast RCC slab including 1/2" thick gola, grouting and jointing including cost of cutting of marble for basin and sink bowl including filling with silicone around joint of marble complete in all respect as per satisfication by the engineer.	Committee of the Committee of C			
	Pantry Counter Top (Boticina)	SFT	20	650-	13000
	1 500M				
8	WOODEN CABINETS Wischen Cobinets				
	Kitchen Cabinets				

				11 11		
1					/ (Carp)	Al .
		Head - A Member	1	1/		
	a		SFT		1500	37000-
	b	<u>Upper Unit:</u> Providing, fabricating and fixing in position pantry cabinets 12" deep and 24" high (Hanging) consisting of 3/4" thick laminated board (Furniture color) of SONEX, AL Noor or equivalent on front shutter and drawers, Dark grey on internal box and shelves moulding 1/2"x3/4" including nails, screws, bolts, imported hinges, catchers, locks, handles, 03 coat of sprit polish of matching shade of furniture color on wood lipping and wood preservative treatment complete in all respects as per drawings and as directed by the bank's Engineer.	SFT	20	Sec	3000 -
9		Paint at Walls				
)	F	Providing and applying, 3 coats of ICI Matt Finish Paint Ash White (3130) or BERGER or equivalent of approved colour and shade, at any floor & at any	OFT	0000	1-	110
	a	neight over one coat of primer and making smooth and even surface by appling ICI Paintex base filling as per specifications, to surface of walls, complete in all respects as specified and as approved by the bank's Engineer.	SFT	2600	63	167000-
10	Z	WOODEN DOOR / FRAME / CHOWKAT /Beading				
а	d ir	DOOR FRAME: Providing and fixing of required width, 16 SWG, GI loor frames for Toilets, kitchen, stores & cash counter with polishing, including Lintels, hold fasts, where ever required, complete in all espect including painting / polish with proper beach / diyar wood eading.	NO	4	7000	28000.
b	sl	KIN DOORS, 1-1/2 inches thick (for Toilets, Kitchen, stores & cash ounter) Provide and install doors consisting of best quality Malaysian kin, pressed over best quality treated partial wood framing, with pproved quality of door locks, handle, tower bolt, hold fast, stopper, ardware and paint /polish, complete in all respect.	SFT	84	Eoo	53400

11	Wooden Hanging Beams.				
	Providing & fixing in postion wooden Beams for support to fix glass and glass door consitsting of 1 1/2 x3" @ 2'-0" c/c partal wood framing and 1/2" MDF Lasani board (Malaysia) on both sides including nails, bolts, glue wastage, wood preservative, treatment & 3 coats of paint complete in all respect as per drawings and as directed by Bank's Engineers.	RFT	30	1350	40500
12	INSTALLATION OF VAULT ROOM DOOR				
	Lifting & Fixing charges of Bank's supplied Vault / Locker Doors, welding of door frame with RCC MS bars, and to facilitate the Vendors. Complete in all respects.	NO	1	2000	2000
13					
14	Providing, fabrication & fixing 12 mm thick glass door with top & bottom locking system, 4" Aluminum D-48 by Lucky or equivalent section, with 12mm thick Middle East / Saudi Arabia or equivalent clear glass with frost film and Bank's monogram, Approved Ajrak film, with gasket size and shape as shown on drawing, including bolts, D lock, nuts, screws aluminum channel, handle, floor machine (New Star or equivalent), locks etc. Complete in all respects as directed by Engineer.		63	1350	8505c.
14	GLASS PARTITION				
	Providing and installation 12mm thick glass KSA/UAEor equivalent polished glass with 100mm top & bottom rails, brush finish SS-304, lucky or equivalent section with frosted film surface as per approved design. Contractor is required to provide joints between the panels with minimum 5mm thick clear silicon from Dow corning or other approved by the Engineer. Complete in all respects.	SFT	100	950.	95000·
15	MARBLE AT ENTRANCE/Stair STEPS				
	Providing and laying 20mm thick Marble of approved quality and size on any type of flooring straight or curved, as per drawings, laid with cement slurry over cement sand mortar (1:4), including filling of joint with grouting material, rubbing, rounding and final chemical polish etc, complete in all respects.	SFT	180	\$50	99000
16	Wrought Iron Grills for external windows, AC outers (If necessary)				
16	type of flooring straight or curved, as per drawings, laid with cement slurry over cement sand mortar (1:4), including filling of joint with grouting material,	SFT	180	\$50	99000



A three feet wide CC ramp, at 30 degree, will be provided for disabled person. The ramp tiles will be grooved tiles and, SS railing will be provided Cost includes all said material, complete in all respect. Pvers at Front with P.C.C Sft 100 2co 2ccto M.S DOOR on Emergency exit, ATM internal & Guard Post Fabricating, providing and fixing MS door with 16 S.W.G M.S 3/4" square pipe, 16 SWG MS sheet pressed over this frame including metal door frame, at both sides, sheet frame painted with approved enamel color including 2" x 5" eye level opening with proper MS shutter of 16 swg sheet to look outside, including best quality hinges, locks, handles, hold fasts and other necessar hardware etc. size as per site. Complete in all respects as per drawing attached herewith, specifications and as directed by the Bank.		Approved design grills for all external windows & Ac Outers/exhaust fans (if required). The security grills will be installed from inside so that glass will be visible from outside. MS Grill comprising of 1/2" solid square bars @ 6" c/c 1"x1-1/2" MS 16 gauge angle iron, welding, grinding, finishing, rubbing 3 coat of enamel paint (ICI,NIPPON,BERGER or equivalent) red oxide before paint. Complete in all respects, as per standardized design and /or as shown in drawing as per approved design, attached herewith. Further proper lockable grills with above specification will also be provided for all AC outdoor units.	SFT	170	550.	93500
person. The ramp tiles will be grooved tiles and , SS railing will be provided Cost includes all said material, complete in all respect. Pvers at Front with P.C.C Sft 100 2co 2cott M.S DOOR on Emergency exit, ATM internal & Guard Post Fabricating, providing and fixing MS door with 16 S.W.G M.S 3/4" square pipe, 16 SWG MS sheet pressed over this frame including metal door frame, at both sides, sheet frame painted with approved enamel color including 2" x 5" eye level opening with proper MS shutter of 16 swg sheet to look outside including best quality hinges, locks, handles, hold fasts and other necessary hardware etc. size as per site. Complete in all respects as per drawing attached herewith, specifications and as directed by the Bank.	17	ATM ACCESS RAMP FOR DISABLED PERSON				
Fabricating, providing and fixing MS door with 16 S.W.G M.S 3/4" square pipe, 16 SWG MS sheet pressed over this frame including metal door frame, at both sides, sheet frame painted with approved enamel color including 2" x 5" eye level opening with proper MS shutter of 16 swg sheet to look outside, including best quality hinges, locks, handles, hold fasts and other necessary hardware etc. size as per site. Complete in all respects as per drawing attached herewith, specifications and as directed by the Bank.		person. The ramp tiles will be grooved tiles and, SS railing will be	No	1	35000	3500c
Fabricating, providing and fixing MS door with 16 S.W.G M.S 3/4" square pipe, 16 SWG MS sheet pressed over this frame including metal door frame, at both sides, sheet frame painted with approved enamel color including 2" x 5" eye level opening with proper MS shutter of 16 swg sheet to look outside, including best quality hinges, locks, handles, hold fasts and other necessary hardware etc. size as per site. Complete in all respects as per drawing attached herewith, specifications and as directed by the Bank.		Pvers at Front with P.C.C	Sft	100	200	20000-
Fabricating, providing and fixing MS door with 16 S.W.G M.S 3/4" square pipe, 16 SWG MS sheet pressed over this frame including metal door frame, at both sides, sheet frame painted with approved enamel color including 2" x 5" eye level opening with proper MS shutter of 16 swg sheet to look outside, including best quality hinges, locks, handles, hold fasts and other necessary hardware etc. size as per site. Complete in all respects as per drawing attached herewith, specifications and as directed by the Bank.						,
16 SWG MS sheet pressed over this frame including metal door frame, at both sides, sheet frame painted with approved enamel color including 2" x 5" eye level opening with proper MS shutter of 16 swg sheet to look outside, including best quality hinges, locks, handles, hold fasts and other necessary hardware etc. size as per site. Complete in all respects as per drawing attached herewith, specifications and as directed by the Bank.	17	M.S DOOR on Emergency exit, ATM internal & Guard Post				
AND DESCRIPTION OF THE PROPERTY OF THE PROPERT		16 SWG MS sheet pressed over this frame including metal door frame, at both sides, sheet frame painted with approved enamel color including 2" x 5" eye level opening with proper MS shutter of 16 swg sheet to look outside including best quality hinges, locks, handles, hold fasts and other necessary hardware etc. size as per site. Complete in all respects as per drawing attached herewith, specifications and as directed by the Bank.	300 RM			42750 -
		TOTAL CIVIL WORK		1	-a 4	,,,,,



_	-				
.No.	DESCRIPTION	UNIT	QTY	Rate	Amount
<u>1. II</u>	NTERNAL WIRING				
1	Supply, installation and commissioning of Light Circuit wiring, from MCB in DB to Switch Board to be wired with 3x2.5mm sq. (P+N+PE) PVC insulated 300/500 V grade wire, manufactured by M/s. "AGE, Pioneer, FASTor equivalent, or as specified in Annexure A, in and including cost of 1" dia. heavy duty PVC conduit make Popular, Beta, installed on roof slab, above false ceiling, or concealed in walls, or as required as per site conditions, all PVC conduit accessories, pull boxes, steel pull wires, Complete in all respects. Each circuit shall have independent CPC. Maximum wiring of 2 light circuits can be pulled through 1" dia. PVC conduit.				
		Nos.	6	4200	24000
2	Providing, Installation, testing and commissioning of wiring of One light point controlled by one switch and wired with 3x1.5 mm sq. PVC insulated wires 300/500 V grade, in and including cost of 3/4" dia. heavy duty PVC conduit recessed in wall, columns slabs or above light carrier all PVC conduit accessories, 3" high PVC junction boxes, pull boxes, steel pull wires, PVC flexible conduit from ceiling junction box to light fixture with brass chuck nut including cost of 3x1.5mm sq from Ceiling Junction Box to Light Fixture, M.S. sheet steel switch box 16 SWG with earth terminal and 2 coats of enameled paint, M.S. box shall be of the same size as that of 1, 2 or 3 gang flush type plate switches, including cost of gang type light switches 10 amps.				
		Nos.	4	3000	12000

SIGNATURE NEW PROPERTY.

Head - Fin Div.

Mentschild Liv.

4		ATURE	MA	IBERS	MC-ADMII
3	Providing, Installation, testing and commissioning of wiring of Two light points controlled by one switch and wired with 3x1.5 mm sq. PVC insulated wires 300/500 V grade, in and including cost of 3/4" dia. heavy duty PVC conduit recessed in wall, columns slabs or above light carrier all PVC conduit accessories, 3" high PVC junction boxes, pull boxes, steel pull wires, PVC flexible conduit from ceiling junction box to light fixture with brass chuck nut including cost of 3x1.5mm sq from Ceiling Junction Box to Light Fixture, M.S. sheet steel switch box 16 SWG with earth terminal and 2 coats of enameled paint, M.S. box shall be of the same size as that of 1, 2 or 3 gang flush type plate switches, including cost of gang type light switches 10 amps.	Fin Div. Admin I or-IDBL Date:	JV.		
) .		Nos.	10	4500	4500
4	Providing, Installation, testing and commissioning of wiring of Three light points controlled by one switch and wired with 3x1.5 mm sq. PVC insulated wires 300/500 V grade, in and including cost of 3/4" dia. heavy duty PVC conduit recessed in wall, columns slabs or above light carrier all PVC conduit accessories, 3" high PVC junction boxes, pull boxes, steel pull wires, PVC flexible conduit from ceiling junction box to light fixture with brass chuck nut including cost of 3x1.5mm sq from Ceiling Junction Box to Light Fixture, M.S. sheet steel switch box 16 SWG with earth terminal and 2 coats of enameled paint, M.S. box shall be of the same size as that of 1, 2 or 3 gang flush type plate switches, including cost of gang type light switches 10 amps.				
		Nos.	15	4500	67500-
5	Same as Item No. A.02 mentioned above, but wiring of Wall Bracket Fan points including cost of M.S sheet steel switch box 16 SWG with earth terminal 1-10 Amps gang type switch make CLIPSAL (Australia), PDL (New Zealand), ABB (Italy), MK (UK), Legrand (France).	Nos.	2	3 <i>5</i> 00	7000 -
6	Confirming to same specifications as mentioned above in Item No. A.02 but wiring of Exhaust Fan points , including cost of hook box and cost of 10 Amp switch make Clipsal M.S box 16 SWG with earth terminal, 2 coats of antirust point, all fixing accessories, 1-5 Amps ceiling rose and including one switch of 10 amps switch, make CLIPSAL (Australia), PDL (New Zealand), ABB (Italy), MK (UK), Legrand (France)	No.	3	35 co	10500

Tender Document - RENOVATION WORKS- SHAH LATIF Providing & wiring of 1-3 pin 15 Amps power socket outlets (for General Use) wired with 2x4mm2+1x2.5mm² CU/PVC insulated cable 300/500 Volt grade, make Pakistan cables, Fast, Pioneer in 25mm dia PVC conduit make Beta, Popular, recessed in wall/floor, above false ceiling or as required as per site conditions, all PVC conduit make Beta accessories, pull boxes, steel pull wires. Complete with all conduit & wiring accessories including 15 Amps, 3 pin combined switch socket make Clipsal (Austria), Panduit ,MK(UK), Legrand (France) or approved equivalent. Wiring shall be done directly from the MCB installed in the respective DB without any claim of circuit. complete with suitable size 1.5mm thick sheet steel back box recessed in wall. 20000 Soo Nos. 8 Providing & wiring of 1-3 pin 10 Amps power switch socket outlets (for RAW supply / WAPDA) wired with 3x2.5mm2 1 core CU/PVC insulated cable in 25mm dia PVC conduit make Beta, Popular, recessed in wall/floor, above false ceiling or as required as per site conditions, all PVC conduit make Beta accessories, pull boxes, steel pull wiresetc. Complete will all conduit & wiring accessories including 10 Amps, 3 pin combined switch socket make Clipsal (Austria), MK(UK), Legrand (France) or approved equivalent. Wiring shall be done directly from the MCB installed in the respective DB without any claim of circuit. complete with suitable size 1.5mm thick sheet steel back box recessed in wall. 2000 5000 Nos. Confirming to same specification as mentioned above in item A-08, but outlet i) 3000 to outlet wiring. Complete in all respect. 500 Nos. Providing & wiring of 2-3 pin 13 Amps power switch socket outlets (for UPS) 9 wired with 3x2.5mm2 1 core CU/PVC insulated cable in 25mm dia PVC conduit make Beta, Popular, recessed in wall/floor, above false ceiling or as required as per site conditions, all PVC conduit make Beta accessories, pull boxes, steel pull wires. Complete will all conduit & wiring accessories including 13 Amps, 2/3 pins combined switch socket (duplex) make Clipsal (Austria), MK(UK), Legrand (France) or approved equivalent. Wiring shall be done directly from the MCB installed in the respective DB without any claim of circuit. complete with suitable size 1.5mm thick sheet steel back box recessed in wall. 5000 Nos.



Letter of Acceptance

Date: 17/10/2022

To: M/s. R.R Associate & 18-C, Mezzanine Floor, Stadium Lane-3, Phase – V, D.H.A Karachi

Subject: Renovation of Shah Latif Town Branch Karachi

Notification of Award of Contract No: SNDB/COK/ADMIN/TD/1263/2022

This is to notify you that your Bid dated $\frac{23}{3}$ for execution of then & SNDB/COK/ADMIN/TD/1263/2022 for the accepted contract amount of the equivalent of (Rs.3,794,350/- & Rupees: Three Million Seven Hundred Ninty Four Thousand and Three Hundred Fifty Only) as corrected and modified in accordance with instructions to bidders is hereby accepted by our agency.

You are requested to furnish the Performance Security within 28 days in accordance with the conditions of Contract, using for that purpose the Performance Security Form included in the bidding document and sign the contact agreement attached herewith within stipulated time mentioned above.

Arshad Abbas Soomro

Head of Administration & Chief Security Officer

Sindh Bank Ltd

www.sindhbank.com.pk :---